

1 DRUG SUBSTANCE - PCS PANEL LOCATION PLAN - WALKABLE CEILING

78-1-2-4-25 SCALE: 1:100

REVISION C NOTES / NOTAS DE REVISÃO C

ADDED NEW PCS INSTRUMENTS ACCORDING TO LAST VERSION OF THE P&ID'S DIAGRAMS.

ADICIONADO NOVOS INSTRUMENTOS PCS DE ACORDO COM A ÚLTIMA VERSÃO DO DIAGRAMA P&ID'S.
ADDED NEW CABLE TRAYS TO WIRED PCS INSTRUMENTS & VENDOR PANELS. ADICIONADO NOVAS ELETROCALHAS AOS INSTRUMENTOS E PAINÉIS DE FORNECEDORES.

REVISION 0 NOTES / NOTAS DE REVISÃO 0

REMOVED PANELS FOR FIRST FLOOR REMOVIDOS OS PAINÉIS PARA O PRIMEIRO PISO.

REVISION 1 NOTES / NOTAS DE REVISÃO 1

UPDATED ACCORDING NEW SKID SCOPE DEFINITION; ATUALIZADO DE ACORDO COM A NOVA DEFINIÇÃO DE ESCOPO DO SKID.
PANEL DIMMENSIONS SHALL BE CERTIFIED AFTER ACQUISITION. DIMENSÕES DE PAINÉIS DEVERÃO SER CERTIFICADAS APÓS A

REVISION 2 NOTES / NOTAS DE REVISÃO 2

TRANSLATED TO PORTUGUESE. TRADUZIDO PARA PORTUGUÊS. REVIEW ACCORDING PROCESS UPDATE. REVISÃO DE ACORDO COM A ATUALIZAÇÃO DO PROCESSO.

Project Services 721 ARBOR WAY, SUITE 100 PENNSYLVANIA 19422 Engineering Design/Build PHONE: 610.828.4090 FAX: 610.828.3656 Compliance

Consulting www.ipsdb.com IPS Professional Engineers and Architects, PC.

BLUE BELL

	REV	DATE	DESCRIPTION	BY	CHECK	APPF
	Α	28AUG2020	90% BD ISSUE	MAV	MAF	MSS
Ī	В	16OCT2020	FINAL BD ISSUE	LCO	MAF	MSS
	С	05JUL2021	90% DD ISSUE	ACC	MAF	RSP
	0	31JUL2021	ISSUE FOR CONSTRUCTION	ACC	MAF	RSP
	1	10NOV2021	ISSUE FOR CONSTRUCTION CONSIDERING COMMENTS	AG	MAF	RSP
	2	11FEB2022	ISSUE FOR CONSTRUCTION CONSIDERING COMMENTS	ACC	MAF	RSP
ļ						
ļ						
ļ						
ļ						
- 1						



R. Dr. Cesário Mota Júnior, 424 - Vila Buarque, São Paulo - SP, 01221-020

GENERAL NOTES / NOTAS GERAIS:

THE INSTRUMENTS AND VALVES COMPONENTS OF SKIDS WILL HAVE THEIR POSITIONING DEFINED BY THE SUPPLIER OF EACH SKID. SO ALSO REGARDING THE SKID CONTROL PANELS, INSTRUMENT PANELS AND JUNCTION BOXES; OS INSTRUMENTOS E VÁLVULAS COMPONENTES DOS SKIDS TERÃO (POSICIONAMENȚO DEFINIDO PELO FORNECEDOR DE CADA SKID. DE ACORDO TAMBÉM COM O PAINEL DE CONTROLE, PAINEL DE INSTRUMENTOS E CAIXAS DE JUNÇÃO.


PARA ALTURA DE MONTAGEM, VER O DETALHE TÍPICO DE INSTALAÇÕES. THE MOUNTING HEIGHTS OF VALVES AND DEVICES MUST CONFORM


A ALTURA DE MONTAGEM DAS VÁLVULAS E DISPOSITIVOS, DEVERÁ


INSTRUMENT MOUNTING HEIGHTS SHOULD OBSERVE THE TYPICAL

SER CONFOME O ISOMÉTRICO DE TUBULAÇÃO. THE MOUNTING HEIGHT OF PANELS SHOULD BE SUCH THAT IT ALLOWS EASY ACCESS AND VIEWING TO MONITORING AND CONTROL A ALTURA DE MONTAGEM DOS PAINÉIS DEVERÃO SER DE FÁCIL ACESSO E VISUALIZAÇÃO PARA MONITORAMENTO E CONTROLE DOS

CONSIDER THE MOUNTING HEIGHTS OF THE CABLE TRAY HAVING TH WALKABLE CEILING AS A REFERENCE LEVEL. CONSIDERAR A ALTURA DE MONTAGEM DAS ELETROCALHAS, TENDO COMO NÍVEL DE REFERÊNCIA O FORRO CAMINHÁVEL.







CONFIDENTIAL

THE INFORMATION CONTAINED HEREIN MAY NOT BE USED OR REPRODUCED IN ANY MANNER WITHOUT WRITTEN PERMISSION OF INTEGRATED PROJECT SERVICES.



DRUG SUBSTANCE PCS PANEL LOCATION PLAN **WALKABLE CEILING**

DRAWN BY REVIEWED BY SCALE

7B-I-2-4-25